G. R. S. 59] GPB 15,000, 20 12 13

GENERAL AND REVENUE SECRETARIAT.

1892-93
~~191~~.
(Murvai)

File No. 280

Serial Nos.

Papers Filed.

Month

SUBJECT.

Construction of a Chauda-
Sala & certain other repairs to the
Ghate Subramanyaswami Temple
Dodballapur Tq

PREVIOUS REFERENCES | LATER REFERENCES.

OFFICE OF THE
3211
12 JUL 90
232

(General Serial No. 31.)

27.1880

From

The Deputy Commissioner
Bangalore District

To

The Chief Secretary to the
Govt of Mysore

Dated 10th
Registered 12
Received 11th July 1870

C Vachaleswara
Ch
12/7/80

Enclosures No. 4

General No.
No. 276

Bringing to notice the difficulty experienced for want of accommodation to travellers in the Ghaute Subramanyaswamy temple, & submitting proposal to restore the temple at a cost of Rs: 8447

Dy Commissioner's Office
Bangalore district
7th-th July 1890

D No 276
Encl 14

To

The Chief Secretary to the
Government of Mysore

Sir,

I have the honor to bring to your notice the extreme hardship pilgrims and travellers are subjected to, for want of accommodation in the Ghati Subramanyaswamy temple, in Doddballapur Taluk, during the Jatra season. Hordes of cattle collect there for sale and trade is carried on very briskly at the time. Above 20,000 people are stated to congregate there every year. The shrine is situated in a desert some twelve miles from the Taluk Head Quarter and there is not a village within two miles of it. Owing to rain last year, the sufferings of people were very great, and it is therefore proposed to restore the ruined temple and build a "Santharpanasala" and a "Chandrasala" for the accommodation of the people, at a cost of Rupees 8247. One Venkatramanachar has proposed to build Mahadwaram at his own cost, and if he does it there will be a lessening of about Rs 250 in the estimate.

The Amildar's urzi and

An accompanying plan and statement are herewith submitted for early sanction

3 The amount is to be met from the savings of Rs 4504 now at credit of the institution and the balance is to be adjusted from its estimated annual receipts of about Rs 1800/— —

4 The work will be given out on contract and as progress of work will necessarily be slow the annual receipts in the coming years will sufficiently meet the expenditure after the present savings are expended

I have the honor to be

Sir

your most obedient servant

Deputy Commissioner

9
F.41

(General Serial No. 30.)

1890.

From

37

To The Dy Commissioner Bangalore Dist

Dated 21

Despatched 23 August/90

Received

Enclosures No. 4

General No. 5693

No. 256

His No. 276 dated 10th ultimo submitting for sanction an estimate amounting to Rs. 8447/ for repairing and improving the temple of Ghati Subramanya Swamy temple, Dodda Ballapur Taluk

I am directed with reference to the above to observe that the cost of blasting and removing boulders amounts to Rs. 40/ only and not Rs. 640 as

shown in the estimate and that as the construction of the new Waterworks, as proposed to be undertaken by the Commissioners at this time, is not included in the estimate, the construction thereof may be omitted.

2. As the Temple Fund has not sufficient funds now at its credit to meet the cost of all the works now proposed to be carried out, the Board is of opinion that the construction of one or two new buildings ~~shall~~ should be deferred till sufficient funds are accumulated.

3. The estimate and the other enclosures are herewith returned for necessary alterations in the manner specified.

(Sgd) [illegible]

Chairman

[illegible] Secretary

9
F. 41

(General Serial No. 29.)

1890.

From The Dy Commissioner
Bangalore District

To The Chief Secretary to the Dewan of Mysore.

Dated 6th November 1890.

Despatched

Received

Enclosures No. 1 file

General No. — } 188 .
No. 563.

Submits for Sanction
Estimate for Rs: 5,307 for the
construction of the main building
at Chandrasale of the State
Subramaneyaswamy's temple,
Doddaballapur Taluk.

Marzeroy
6/11/90

Recd
22/11/90

33
22-11-90

Final Decision | 561

The Commissioners' Office
Bangalore District
6th November 1890

D. No. 563
Enclosure

To

The Chief Secretary to the
Dewan of Mysore

Sir,

With reference to docket No. 5893/256 dated 21st August last, I have the honour to forward, herewith, revised estimates for improving the Ghats' Subramanyaswamy's temple, Doddaballapur Taluk, received from the Amildar, and to state that the construction of the main building or "Chandrasala", at a cost of Rs. 5307, is reported to be urgent. A sum of Rupees 4,457 2 9 is, at present, at credit of the temple and the balance of Rs 853 13 3 may be availed out of the realizations at

Net Deductions 567

at the next Jatra - I would therefore request that sanction may be accorded to push on with this work.

2 The difference in the item of blasting and removing boulders work, as the rate, per cubic yard, was through an oversight entered at two annas, instead of at two rupees by the Taluk Officials, and the same has been duly corrected - The item of Rs. 150 for the new "- Mahadwaram has accordingly been omitted -

3. Vernacular papers together with the canarese bill bearing the Treasury Officers certificate are forwarded for reference and return -

I have the honor to be

Sir,

Your most obedient servant

M Kumara Rao

for Deputy Commissioner

mes

Estimate of the probable cost for Constructing and Improving Soobba Raja Swamy Temple in Taluk of Kodi Bellapur. Bangalore District

Main Building

40

Details	No.	Measurements L	B	D	contents	Total
Earthwork						
Chandrasale - Foundation to the wall of North end	1	96½	2½	3	724	
Do —— Do —— Do ——	1	81½	2	3	489	
Do —— Do —— South end	1	96½	2½	3	724	
Do Do Do	1	81½	2	3	489	
Do Do East end	1	70½	2½	3	529	
Do Do Do	1	55½	2	3	333	
Do Do West end	1	70½	2½	3	529	
Do Do Do	1	55½	2	3	333	
Do Do steps	2	9	3	1	54	
Filling Basement ——	1	281	6¼	2½	4390	
				Total —	8594	Cy do
			Total Cy do —		318	
			add for Surface Swelling the Compound		100	418
Stone in Clay with bond Stones 10 feet apart ——						
Chandrasale - Filling foundation and Basement						
Wall of North end	1	96½	2¼	6	1303	
Do	1	81½	1¾	6	856	
Do South end —	1	96½	2¼	6	1303	
Do — Do	1	81½	1¾	6	856	
Do East end	1	70½	2¼	6	952	
Do Do	1	55½	1¾	6	582	
Do west end	1	70½	2¼	6	952	
Do Do	1	55½	1¾	6	582	
Steps	2	9	3	1	54	
Do	2	7	2	1	28	
Do	2	5	1	1	10	
					7478	
Deductions - Upright Slabs of Chandrasale	50	1½	½	6	225	
Slabs under Do Do	50	2½	2	½	125	
Slabs over the sill of Do	1	261	1½	½	196	
Slabs over steps of Chandrasale	2	9	1	½	9	
Do ——	2	7	1	½	7	
Do ——	2	5	1	½	5	
			Total Deductions		567	

Total Stone & Clay Bear Deductions

Burnt Brick in clay

Superstructure. Chandrasale Wall to Elev	1	96	1½	7	1008	
do South do	1	96	1½	7	1008	
do East do	1	48	1½	7	504	
do West do	1	71	1½	7	745	
Cross wall of storeroom	1	6½	1½	7	68	
do	1	6½	1½	7	68	
do Yagasale	1	6½	1½	7	68	
do do	1	6½	1½	7	68	
Parapett wall	1	354	1	3	1062	
do	1	254	1	3	762	
					5361	
Deductions - for upraghts of main walls	42	1½	½	7	220	
do do	8	1½	½	6	36	
doorways —	1	4	6	1½	36	
do	1	3	6	1½	27	
windows	4	4	1½	3	72	
Doorway	1	4	6	½	36	
Lintels of windows	2	5	1½	½	8	
do do	1	4	1½	½	3	
do do	4	5	1½	½	15	
Doorway of stone and Yagasale	2	2½	5	1½	37	
Lintels do	2	3	1½	½	4	
Total Deductions —					494	
Total brick in clay less deductions —						4867
Stone Girders with Cutt Chisalled work -						
Chandrasale Upraghts in front	42	1	1	6	252	
Carbles	42	2½	2½	1	263	
Cross Girders	32	10½	1	1	336	
do	4	15	1	1	60	
do	14	8¾	1	1	122	
Total stone Girders with Chisaled work Cft						1033
Stone Girders with ½ Chisalled work						Cft
Carbles	13	2	2	1	52	52
Tin Spouts						
Over the roof of Chandrasale	30	3½	Rft			105
Stone Slabs 6" thick including lifting and fixing &c						
Chandrasale under slabbed upraghts	50	2	2	—	200	
Slabbed upraghts	35	1½	12½	—	656	
do	15	1½	111/2	—	259	
		60	0		1115	

B Fd

					1115	
Slips	1	9	1		9	
Do	1	7	1		7	
Do	1	5	1	"	5	
Lintels over Door	2	5	1½		15	
Do	1	4	1½		6	
Do	2	3	1½		9	
Do over window	4	4	1½	-	24	
over Verandah	1	262	1½	—	393	
Covering slabs	2	97½	10½		2018	
Do	2	55	10½		1155	Sft
Total Stone Slabs					4786	4786
Plastering and Removing Bolders						Cyds
Do	1	10	32	6	1920	71
Chunam Pointing to the Basement-Exterior						
Chandrasale Basement Exterior	2	96½		3	579	
Do	2	52		3	312	
Do	2	79		3	474	
Do	2	73		3	438	Sqrs
Total Chunam Pointing					1803	1803
Chunam Plastering						
Chandrasale Walls to the North and South End	2	96	.	7	1344	
Do	2	93	"	7	1302	
Do West End	1	71		7	497	
Do Do	1	68	"	7	476	
Do East End	2	33		7	462	
Do Do	2	30		7	420	
Crosswalls of Jagusale and Stone room	4	6¼	.	7	175	
Parapel walls	1	354		6	2124	24 sqrs
Do	1	254		6	1524	
Total Sqrs Chunam Plastering					8324	83·24
Whitewashing						
As per Chunam Plastering				83 sqrs		83·24
Concrete flooring including Chunam Plastering						
Chandrasale North End	1	37½	6	½	113	
Do	1	37½	6	½	113	
South End	1	79½	6	½	238	
West End	1	71	6	½	213	
East End	1	26	6	½	78	
Do	1	26	6	½	78	
Over the roof	1	304	6½	1	1976	
over old Temple	1	27	31¼	½	422	
Do	1	18	13	½	117	
Total concrete flooring					3 [illegible]	

Wood oiling 2 Coats						
For doors	2	6	3	...	36	—
" Do	2	4	6	"	48	
Windows	8	4	3	"	96	
Doors	4	5	2½	"	50	
Total wood oiling two coats					230	2·30
Jungle wood doors with hooks and folding & complete						
Door	1	(6 × 3)		"	1	1
Do	1	(6 × 4)		"	1	1
Do	2	(5 × 2½)			2	2
Jungle wood windows with Iron bars and shutters &c complete						
Windows	4	(4' × 3')		"	4	4
Petty Repairs						
Constructing new Mahadrawa at the Entrance	1		Item		1	1
Constructing new Tower "Gopuram" with ornamental work over Chandrasale	1		Item		1	1
Repairs to old Tower of Garbadevasthana	1		Item		1	1
Repairs to old Temple where ever necessary	1					
	1		Item		1	1
Dismantling and removing old ruined walls and Mandapums in the Compound	1		Item		1	1
Clearing site of the Compound		1	Item		1	1

Abstract of Estimate

Items	Rate			Per	Main Building	
					Quantity	Cost
Earth work		2	..	Cyds	418	5-2
Stone in clay with bond stones 10 feet apart		1	8	Cft	6911	720
Burnt brick in clay	..	1	9	Cft	4867	532
Stone Girders with cutt Chisaled work	..	10	..	Cft	1033	646
Stone Girders with ½ chisaled work	..	7	..	Cft	52	23
Tin Spouts	..	3	..	Rft	105	20
Stone Slabs 6" thick including lifting and fixing &c	..	3	6	Sft	4786	1047
Blasting and removing Boulders	2	..	..	Cyd	71	142
Chunam Pointing	1	8	..	Sqr	18·03	27
Chunam Plastering	2	8	..	Sqr	83·24	208
Mud Plastering	..	6	..	Sqr	..	..
Cowdung washing	..	..	9	Sqr	..	..
whitewashing	..	3	..	Sqr	83·24	15
Concrete flooring including Chunam Plastering	..	3	6	Cft	3248	711
Gravelling	..	5	.	Cyd	..	..
Wood oiling 2 coats	2	..	..	Sqr	2·30	4
Jungle wood Doors with hooks & foldings &c complete (6'x3')	20	..	..	Each	1	20
(11'x4')	2			Each	1	2

Do Do (5'X2½)	15	..	..	Each	2	30
Simple wood Windows with Iron bars & shutters &c Complete						
Do Do (4'X3)	8	..	..	Each	4	32
Petty Jobs Constructing new Mahadvara at the entrance	150	..	..	Item	1	150
Constructing New Tower "Gopuram" with the ornamental work over Chandrasale	300	..	.	Item	1	300
Repairs to old Tower of Garbha Devastana with ornamental works	200	..	..	Item	1	200
Repairs to old Temple walls floor and roof &c	150	..	..	Item	1	150
Dismantling and removing ruined walls & Mantapams in the Compound	100	..	..	Item	1	100
Clearing site of the Compound	50	.	..	Item	1	50
						5204
Deduct the construction of Mahadvara which will be carried out by Venkatramana Chary						150
Total Rupees less Deductions						5054
Add Contingencies at 5 percent						253
Grand Total Rupees						5307

Copied
N.V.R

Read

Letter No. 563 dated 6th Novr./90 from the Dy Commr., Bangalore Dist., submitting for sanction an estimate for Rs. 5307/- for the construction of the main building of Chandrasale of the Ghate Subramanya Swamy temple in the Doddaballapur Taluk.

No 9631-2 dt 26-11-90
394 / 28
E2 T/90.

Order thereon —

The Mustrai Returns and the Voucher statement now submitted by the Dy Commr. show that the sum of Rs. 4451-2-9 said to be now available at the credit of the temple is the aggregate of different items of receipts credited to the head "Receipts of temples", as per

[illegible] instructions laid
down in the late Sir
[illegible] Fortescue Knt
Chancellor of the Exchequer
dated 6th June 1874
and made by Barnfathers
"Stands" as more exactly
specified by the said
Officers of the Treasury
Officers of the Treasury
Official certificate
Numbers corrected
accordingly in red
ink in this office.

2. The estimate of
£5307 is arrived
at and the charges
being made as noted
below:—

From the funds of the Limpet more exactly described under the Head of Limpet	}	P.A. & O. 4451-2-9
Contingencies Victualling Office at the rate of 1/3 of the Limpet	}	855-13-3.
Total		5307-15-0

3. The work will

will be commenced at once on contract as proposed by the Dy Commr and carried out in a substantial manner under the supervision of the Amildar who ~~should be directed to see to the proper execution of the last coating of the work & he should submit a report duly executed and countersigned~~ will be responsible for it & submit a completion report in due course.

2. The construction of the new Mahadwara should as arranged already be undertaken by Venkatramanachary at a cost not less than Rs. 150/ and its progress will be reported on to this office.

Secretary

To The Dy Commr, Bangalore Dist with the saved estimate & the other enclrs.

Comptroller with a copy of the abstract estimate.

Note:- A copy of the estimate to be kept in office.

C.V.

J. 41

1890.

To

The Dy Comm^r Bangalore

Comptroller

Dy 26th Novr 1890.

No. 9631-2 A
394.

Sanct^n Estimate for Rs. 5309
for the construction of the Nan
bathing or Chaudrasalé of
the Sitate Subramanyaswa
Temple in the Doddaballapur



(General Serial No. 30.)

42

1892 – 93

From The Dy Commissioner Bangalore District

To

The ~~Chief~~ Secretary to the Dewan of Mysore.

Bazar Department

Dated 11th January 1893

Despatched

Received

Enclosures No. 14. 1 file

General No.

D No. 607.

In reply to Govt Pro: No 9631-2 dt 1/12/92 394

SUBJECT.

Submits revised Estimate amounting to Rs: 7,359/ for the con-struction of a Chandra-sala in the Shate Subbramaneya swamy Temple Dodda Ballapur Taluk.

References (to be entered only in the Dewan's Office).

Returned to Dy Comr with Govt Order as 14/1/93

To the Same no 692-3 Dno 14/1/93

Mins 88-92

D. No. 607.
Encl. 1 file

Dy. Commissioners Office.
Bangalore District.
Dated 11th January 1893.

To

The Secretary to the Dewan of Mysore
Muzroi Department.

Sir,

In reference to Government Proceedings No. 9631-2/394 dated 1st December 1890, regarding the construction of a Chandrasala to the Ghate Subbramaneyaswamy's Temple, Dodda Ballapur Taluk, I have the honor to state that it would appear that on the present Amildar having brought to the notice of Mr. V. P. Madhava Rao, the difficulty of procuring contractors to carry out the work in consequence of the low rates provided in the old estimate a revised estimate has been prepared

by the D.P.W. Sub Division Officer amounting to Rs: 7,359/
This revised estimate has been certified by the Executive Engineer to be correct.

2. There is at present a balance of Rs: 6,362-11-5 including last years realizations at the Jatra and the difference of about Rs: 1000/. can be met from the collections of this years Jatra, which was lately held.

3. The correspondence ending with Dodda Ballapur Amildar's Wrzee No. 293 dated 1st November/92 is enclosed for reference

I have the honor to be
Sir,
Your Most Obedient Servant
Nagavachar
Dy Commissioner

Read :—

Letter No 607 dated 11th January 1893 from the Deputy Commissioner, Bangalore District, submitting for sanction a revised estimate amounting to Rs 7339/- for constructing the Chowdrasala and executing other repairs to the Shatte Subramanya swamy temple in the Doddaballapur Taluk.

Order thereon

No. 672 F. D. 19/1
M. I. 28, 2

19-1-93

The Dy Commissioner reports that, in consequence of the low rate provided in the estimate

sanctioned for Rs 5307/-
in forth Pro No. 9631-2
28
dated 26th November/90
No contractors came
forward to undertake
the work, that the
temple to which the
repairs have to be
executed is situated
on the top of a hill,
that therefore a revised
estimate is now sub-
mitted for all the
necessary works and
that the Executive Engineer,
Bangalore Division,
certifies that the rates pro-
vided therein are
reasonable.

2 Under the
circumstances reported,
the revised estimate for Rs 7719/-
including of Rs 360/-

being the cost of establish-
-ment, viz, a temporary
overseer for one year at
Rs 30/- per mensem with
effect from 1st May 1893,
~~for Rs~~ is sanctioned,
the charge being met
from the sum of Rs 82-14-1
available at the credit
of the temple on 28th
Feby 1893 under the
head, "Receipts of temples".

3. The old estimate
sanctioned for Rs 5307/-
in favour Pro. above cited
is hereby cancelled.

4. The work will be
commenced at once
and carried out in a
substantial manner
under the superintendence
of the asstt Comr Mr.
B. Kuppusami Naidu

and the general direction of the Mysore Supt.

5. In carrying out the work, arrangements should be made to have sufficient light and ventilation in the temple.

A.S.
Secy.
6.7.1

To

The Dy Comr Bangalore Distt with the sanctioned estimate & other enclosures.

--- Comptroller to the Govt of Mysore with a copy of the abstract estimate.

To the Sanctn 1155-6 & 30/4/92
Mun. 88-92